




Smart. Stylish. Sustainable.
Discover water dispensers
for diverse needs.

Welcome to BRITA VIVREAU





Welcome to BRITA VIVREAU

Smart. Stylish. Sustainable.
Discover water dispensers for diverse needs.



Contents



Industry specific benefits

Offices and industry	6
Hotel, restaurant and catering	7
Hospitals and other healthcare	8
A 360° solution	9

Water dispenser range

BRITA VIVREAU Top 50/85	10
BRITA VIVREAU Extra 50/85	12
BRITA VIVREAU ViTap	14
BRITA VIVREAU Bottler	16

Water treatment technologies

BRITA CLARITY Taste 50/100	20
BRITA CLARITY Protect 100	22
BRITA CLARITY Safe X3	24
BRITA PURITY C Dispenser	26
BRITA Therma Gate™	28
BRITA HygienePlus	29

An end - to - end solution

A range of accessories	31
Customisable BRITA bottles	33
BRITA VIVREAU Service	35








Why choose a BRITA VIVREAU?



You're looking for a water dispenser for your organisation?
You've come to the right place.

If you want to ditch single-use plastic bottles, save time, bolster your bottom line or simply enjoy great-tasting water, or all of the above, you'll find a model to match. The BRITA VIVREAU portfolio comprises a broad choice of mains-fed water dispensers of attractive design, based on outstanding technology. So you will find the right size, capacity, style, features and options for you.

Our passion for water is backed by over 50 years' experience. As a global leader in water filtration technology, we are fully committed to the highest standards of quality and hygiene. We have over 85,000 installed water dispensers worldwide, and dispense water with our BRITA VIVREAU dispensers for over 2.5 Mio people per day. With over 1.4 billion liter great tasting BRITA filtered water per year we quench the thirst of people in companies in various industries from famous car manufacturers, over globally leading hospitality / hotel networks to tech firms from the silicon valley.

-  **Reliable excellence:**
Our family-owned company is committed to delivering exceptionally high standards of quality – with over 5% reinvestment in research & development, we are constantly evolving our technologies.
-  **Outstanding water filtration:**
Our products ensure consistently great-tasting water; we can draw on over 50 years' experience in filtration to create tailor-made answers to your requirements.
-  **Dependable hygiene:**
Special features, such as BRITA HygienePlus, ensure excellent hygiene at all times.
-  **It's a complete solution:**
You enjoy an end-to-end answer to your drinking water needs. We provide a one-stop solution, from installing the dispenser, to maintenance via certified service engineers, to branded bottles and financing options.
-  **Superior sustainability:**
Dispensers cut out the waste and emissions associated with manufacturing, transporting and disposing of single-use bottles.
-  **Enhanced cost-effectiveness:**
Pre-bottled water is not only bad for the environment, it is expensive. Take advantage of water from the mains.
-  **Diverse needs, diverse dispensers:**
Perhaps you want a self-service option for a small group of colleagues (check out BRITA VIVREAU Top 15). Or perhaps you need to fill hundreds of glass bottles, and fast (that'll be our BRITA VIVREAU Bottler). Or you would like certain types of water (hot, sparkling, etc.)? We have an answer to your specific requirements.



Our sustainable alternative for premium water



BRITA VIVREAU water dispensers are a simple and refreshing way to go green – without compromising on taste or quality.

At BRITA, the environment is a topic close to our hearts. That's why we are committed to improving sustainability – at our enterprise, and at yours. We have a recycling programme for our filter cartridges. We are exploring ways to cut carbon emissions through efficient processes. And we are reducing waste throughout the product lifecycle, e.g. by adopting LED lighting and minimising packaging.

If you are looking for ways to shrink your carbon footprint, replacing plastic bottles with a dispenser is an easy way to make a difference:




Less plastic waste

Just consider: if a typical employee drinks one litre of water each workday, then a company of 100 could avoid a whopping 506 kg of single-use plastic waste every year by switching to a BRITA VIVREAU dispenser.*



Skip the refrigerator

The dispensers have a built-in cooler – meaning you can enjoy chilled water at any time, on demand – there's no need for power-hungry refrigerators.



Long service life

BRITA filtration technology helps safeguard dispensers against fine particles such as rust and sand. This extends the life of the equipment – a further plus for the planet.



The right accessories

Our glass bottles are made in Europe and 100% reusable. Moreover, glass is durable, recyclable and made from natural materials. You can fill the bottles on site with freshly filtered water, reducing the impact on the environment.



Cut down emissions

Dispensers cut out the costs, waste and CO₂ emissions associated with buying, transporting and storing bottles. It's eco-friendlier, and it's convenient.

Are you looking for ways to shrink your carbon footprint?

Replacing plastic bottles with long-lasting BRITA bottles and corresponding accessories is an easy way to make a difference.



* Erarbeitung eines Leitfadens zur Erstellung kommunaler Abfallvermeidungskonzepte (available in German only; lit. Guide to Avoiding Waste at Local Authority Level), Bavarian State Ministry of the Environment and Consumer Protection, 2016

Offices and industry

Great-tasting water for greater productivity.



In many offices, pre-filled bottles are a common way of providing consistently high-quality, great-tasting water.

The result, however, is significant plastic waste. What's more, it's expensive and time-consuming: it means the company or individual employees must buy and bring the bottled water themselves, or organise its supply, logistics and storage. Water dispensers do away with these issues and costs at a stroke. They ensure a convenient supply of consistently excellent water, encouraging hydration – and, in turn, helping employees to feel and be their best.

After all, water from the mains is the most carefully controlled foodstuff there is, guaranteed by regional suppliers. What's missing are technologies, including filtration at the point-of-use, heating, cooling and carbonisation, that deliver a great taste. And that is where dispensers come in.

Benefits

- More sustainable – a convenient, eco-friendly alternative to single-use bottles.
- Highly efficient – no need for costly purchase, transportation and storage of pre-bottled water.
- Greater well-being – encourages hydration, improving productivity and satisfaction.

Where to serve BRITA VIVREAU water?

- Meeting rooms
- Reception areas
- Kitchenettes
- Waiting areas
- Canteens



Hotel, restaurant and catering

Enjoy water à la carte.



BRITA VIVREAU dispensers deliver great-tasting water on demand. Offer your visitors and guests the very best – in your hotel, restaurant, bar or conference room.

All you need is mains water. The dispenser takes care of the rest. It transforms your tap water into a delicious beverage, one that reflects the quality of your establishment. Filtration removes impurities to improve taste, for greater customer satisfaction. And you can replace those expensive, wasteful single-use bottles with reusable BRITA designer bottles, optionally branded with your logo.

The result is not just added value, but also potentially added profitability. You enjoy a complete solution that delivers outstanding cost-efficiency and a smaller ecological footprint. And you can proudly serve guests your very own water – regional, refreshing, remarkable – chilled, still or sparkling, according to their preferences.

Benefits

- More sustainable – a convenient, eco-friendly alternative to single-use pre-bottled water.
- Enhanced identity – delicious water, dispensed in designer bottles with your logo.
- Cost-effective – no more procuring single-use bottled water; a potential source of revenue.

Where to serve BRITA VIVREAU water?

- Bars/Restaurants
- Meeting rooms
- Guest rooms
- Wellness areas
- Staff rooms



Hospitals and other healthcare

H₂O: the formula for good health.



Water in hospitals and other healthcare settings must meet exceptionally strict standards.

Robust hygiene is essential to minimising the risk of infection. At the same time, ensuring cost-efficiency is important. And staying hydrated is vital to well-being - especially in healthcare, where swift patient recovery and recuperation is critical.

BRITA VIVREAU water dispensers are an effective answer to these challenges. Patients, visitors and staff can enjoy filtered water free of charge, self-served or brought to them in bottles. It's reliable, refreshing, tasty and - thanks to BRITA HygienePlus - hygienic and safe.

Decades' experience in the deployment of water dispensers in healthcare environments makes BRITA your ideal partner. Specialised solutions include disposable or reusable bottles in accordance with applicable hygiene regulations.

Benefits

- Reliably refreshing - a dependable, convenient source of great-tasting water available on demand for patients, visitors and staff.
- More sustainable - an eco-friendly and cost-effective alternative to single-use plastic bottles.
- Exceptionally hygienic - BRITA HygienePlus based on 20+ years' experience in the healthcare market.

Where to serve BRITA VIVREAU water?

- Inpatient care
- Outpatient care
- Area for staff
- Administration areas
- Training rooms



A 360° solution

BRITA VIVREAU – for total peace of mind.




VIVREAU Top 50/85

Versatility meets reliability.




Medium or high capacity versions



Easy Access Panel
additional control device
(can be optionally installed
and flexibly positioned)

The BRITA HygienePlus solution (which combines an inlet filter, thermal disinfection, and a bacterial filter) provides effective protection for dispensers. Developed on the basis of over 20 years' experience in the healthcare market, it is designed for environments where hygiene is of the utmost importance, and is optionally available for BRITA VIVREAU Top 50/85.



- Intuitive display and choice of buttons
choice of touch or mechanical buttons to select water type

- **ThermalGate™**
Unique thermal-disinfection feature supplied as standard

- High-quality materials
stainless steel

- **Focus on sustainability**
R290 natural refrigerant and extremely low power consumption

Ideal for e.g.


- Staff rooms
- Reception areas
- Lobbies
- Meeting rooms
- Gyms and fitness zones

Benefits

- Unlimited unchilled still or chilled still, sparkling or semi-sparkling water
- BRITA's ThermalGate™ feature protects against retrograde contamination from external sources
- Capacity: 50 l/h or 85 l/h


Two installation options

- Countertop
- Floorstanding



VIVREAU Top 50/85

Technical data



Model	BRITA VIVREAU Top 50	BRITA VIVREAU Top 85	Base cabinet (optional)	Easy Access Panel (optional)
Design / Type	Countertop	Countertop		
Types of water				
Unchilled still	•	•		•
Chilled still	•	•		•
Semi-sparkling	•	•		•
Sparkling	•	•		•
Configuration options				
Hygiene feature: ThermalGate™		standard		
Hygiene feature: BRITA HygienePlus		optional		
Dispensing buttons: Touch		standard		
Dispensing buttons: Mechanical		optional		
Waste water container (installation without waste water connection)		optional		
Specifications				
Cooling capacity	50 l/h	85 l/h		
Unit dimensions (W x H x D)	278 x 530 x 518 mm		278 x 1430 x 518 mm	flat: 80 x 80 x 116 mm angled: 80 x 80 x 137 mm
Dispensing height	330 mm			
Weight	35 kg	40 kg	7 kg	
Max. power consumption	440 W	540 W		
Max. flow rate	2 l/min			
Order number				
System with ThermalGate™ (touch display)	1034122 VIV T 50 C2-TG-I-CU GB	1034136 VIV T 85 C2-TG-I-CU GB	1033790 VIV Top Base Cabinet	1040230 VIV Easy Access Panel
System with BRITA HygienePlus (touch display)	1034123 VIV T 50 C2-HP-I-CU GB	1034137 VIV T 85 C2-HP-I-CU GB	1033790 VIV Top Base Cabinet	1040230 VIV Easy Access Panel
System with ThermalGate™ (mechanical buttons)	1041283 VIV T 50 M-C2-TG-J CU GB	1041296 VIV T 85 M-C2-TG-J CU GB	1033790 VIV Top Base Cabinet	1040230 VIV Easy Access Panel
System with BRITA HygienePlus (mechanical buttons)	1041289 VIV T 50 M-C2-HP-J CU GB	1041302 VIV T 85 M-C2-HP-J CU GB	1033790 VIV Top Base Cabinet	1040230 VIV Easy Access Panel
Waste water container	1041216 VIV Waste Water Container-SP			

The food-grade quality and safety of BRITA water filter products are tested and verified by independent institutions



*applies to all materials that come into contact with water

Contact your BRITA authorized distributor in Egypt | www.quanta-egypt.com


VIVREAU Extra 50/85

Stylishly minimalistic.



ThermalGate™

Powerful thermal-disinfection feature supplied as standard and protects against retrograde contamination from external sources



Easy Access Panel
additional control device
(can be optionally installed and flexibly positioned)

The BRITA HygienePlus solution (which combines an inlet filter, thermal disinfection, and a bacterial filter) provides effective protection for dispensers. Developed on the basis of over 20 years' experience in the healthcare market, it is designed for environments where hygiene is of the utmost importance, and is optionally available for BRITA VIVREAU Extra 50/85.



• Medium or high capacity versions

• High-quality materials stainless steel

• Focus on sustainability R290 natural refrigerant and extremely low power consumption

Ideal for e.g.


- Executive lounges
- Bars
- Kitchenettes
- Breakfast buffets
- Staff rooms
- Wellness and spa areas

Benefits

- Unlimited unchilled still or chilled still, sparkling or semi-sparkling water
- Only the tap is installed on the work surface; the cooler-carbonator is concealed below the counter
- Capacity: 50 l/h or 85 l/h



Two heights

- Tall tap (dispensing height: 330 mm)
- Short tap (dispensing height: 260 mm)



VIVREAU Extra 50/85

Technical data



Model	BRITA VIVREAU Extra 50	BRITA VIVREAU Extra 85	
Design / Type	Tap System		Easy Access Panel (optional)
Tap style	I-Shape		
Types of water			
Unchilled still	•	•	•
Chilled still	•	•	•
Semi-sparkling	•	•	•
Sparkling	•	•	•
Configuration options			
Hygiene feature: ThermalGate™	standard		
Hygiene feature: BRITA HygienePlus	optional		
Waste water container (installation without waste water connection)	optional		
Specifications			
Cooling capacity	50 l/h	85 l/h	
Unit dimensions: cooler-carbonator (W x H x D)	272 x 490 x 473 mm		
Unit dimensions	tall tap (H x D; Diameter): 453 x 165 mm; 70 mm short tap (H x D; Diameter): 385 x 165 mm; 70 mm		flat (W x H x D): 80 x 80 x 116 mm angled (W x H x D): 80 x 80 x 137 mm
Dispensing height	330 mm (tall tap) 260 mm (short tap)		
Weight	33 kg (cooler-carbonator) / 2.5 kg (tap)	38.5 kg (cooler-carbonator) / 2.5 kg (tap)	
Max. power consumption	440 W	540 W	
Max. flow rate	2 l/min		
Order number			
System with BRITA ThermalGate™	1034261 VIV E 50 I-33-C2-TG-I-CU GB (tall tap) 1038060 VIV E 50 I-26-C2-TG-I-CU GB (short tap)	1034272 VIV E 85 I-33-C2-TG-I-CU GB (tall tap) 1038073 VIV E 85 I-26-C2-TG-I-CU GB (short tap)	1040230 VIV Easy Access Panel
System with BRITA HygienePlus	1034267 VIV E 50 I-33-C2-HP-I-CU GB (tall tap) 1038054 VIV E 50 I-26-C2-HP-I-CU GB (short tap)	1034278 VIV E 85 I-33-C2-HP-I-CU GB (tall tap) 1038066 VIV E 85 I-26-C2-HP-I-CU GB (short tap)	1040230 VIV Easy Access Panel
Waste water container	1041216 VIV Waste Water Container-SP		

The food-grade quality and safety of BRITA water filter products are tested and verified by independent institutions



*applies to all materials that come into contact with water

Contact your BRITA authorized distributor in Egypt | www.quanta-egypt.com

VIVREAU ViTap

A stylish dispenser for chilled, sparkling and hot water.




Benefits

- Attractive design; easy to use
- Various combinations of chilled, sparkling and hot water to suit every environment
- Only the tap is installed on the work surface; the cooler-carbonator and boiler are concealed in the base cabinet

Two heights

- ViTap (dispensing height: 240 mm)
- ViTap Plus (dispensing height: 340 mm)



Anti-scalding feature for hot water

Easy-to-clean removable nozzles



Choice of up to five different configuration options



Stainless steel tap

Drip tray with direct connection to waste water system

Perfect water flow with zero splash

Ideal for e.g.

- Executive lounges
- Bars
- Kitchenettes
- Breakfast buffets
- Staff rooms
- Wellness and spa areas

VIVREAU ViTap

Technical data



Model	BRITA VIVREAU ViTap 301	BRITA VIVREAU ViTap 302	BRITA VIVREAU ViTap 303	BRITA VIVREAU ViTap 304	BRITA VIVREAU ViTap 305
Design / type	Tap System				
Types of water					
Chilled still	•	•	–	•	•
Sparkling	–	•	–	–	•
Hot	–	–	•	•	•
Specifications					
Cooling capacity	60 l/h				
Fits into base cabinet with the following dimensions (W x H x D)	300 x 800 x 600 mm	500 x 800 x 600 mm	300 x 800 x 600 mm	600 x 800 x 600 mm	600 x 800 x 600 mm
Unit dimesions under the sink (W x H x D)	210 x 440 x 360 mm (cooler)	360 x 440 x 360 mm (cooler-carbonator)	130 x 523 x 320 mm (boiler)	210 x 440 x 360 mm (cooler) 130 x 523 x 320 mm (boiler)	360 x 440 x 360 mm (cooler-carbonator) 130 x 523 x 320 mm (boiler)
Unit dimensions incl. drip tray (W x H x D)	ViTap standard: 138 x 325 x 165 mm ViTap Plus Upgrade Kit: 210 x 420 x 230 mm (order number: 1023678)				
Dispensing height	ViTap standard: 240 mm ViTap Plus Upgrade Kit: 340 mm (order number: 1023678)				
System weight	19 kg (cooler) 1.6 kg (tap)	39 kg (cooler-carbonator) 1.6 kg (tap)	7.5 kg (boiler) 1.6 kg (tap)	19 kg (cooler) 7.5 kg (boiler) 1.6 kg (tap)	39 kg (cooler-carbonator) 7.5 kg (boiler) 1.6 kg (tap)
Max. power consumption	240 W	520 W	2800 W	3040 W	3320 W
Max. flow rate	2 l/min				
Specifications: Hot water					
Dispensing capacity	–	–	3-4 cups per minute at up to 95 °C		
Boiler tank capacity	–	–	4.5 l		
Order number					
	1032393 ViTap 301-G-1-TS-0 CU GB	1032399 ViTap 302-G-2-TS-0 CU GB	1032407 ViTap 303-G-H-TS-0 CU GB	1032413 ViTap 304-G-1H-TS-0 CU GB	1032419 ViTap 305-G-2H-TS-0 CU GB

The food-grade quality and safety of BRITA water filter products are tested and verified by independent institutions



*applies to all materials that come into contact with water

Contact your BRITA authorized distributor in Egypt | www.quanta-egypt.com

VIVREAU Bottler

A high-capacity dispenser solution.



Easy-to-use lever-type dispenser tap



Flow rate up to 3 l/min

Stainless steel taps

Stainless steel drip tray
Plumbed-to-waste option

Easy-to-clean removable nozzles

Ideal for e.g.

- Back of house pantry for conferences, banquets or restaurants
- Bars
- Breakfast buffets

Benefits

- Dispenses high volumes of chilled still and sparkling water on demand
- High-performance ice-bank refrigeration for chilled water at consistently low temperatures
- Capacity: 80 l/h or 180 l/h


Three installation options

- Countertop
- Floorstanding
- Tap system



VIVREAU Bottler

Technical data



Model	BRITA VIVREAU Bottler 101	BRITA VIVREAU Bottler 102	BRITA VIVREAU Bottler 103	BRITA VIVREAU Bottler 104	BRITA VIVREAU Bottler 105
Design / Type	Floorstanding	Floorstanding semi integrated	Tap system	Countertop	Tap system
Types of water					
Chilled still	•				
Sparkling	•				
Specification					
Cooling capacity	180 l/h			80 l/h	
Fits into base cabinet with the following dimensions (W x H x D)	-	-	700 x 800 x 600 mm	-	600 x 800 x 600 mm
System dimensions (W x H x D)	595 x 850 x 590 mm (base cabinet only) 180 x 490 x 220 mm (tap) 595 x 1335 x 590 mm (total system)	595 x 850 x 590 mm (system cabinet) 180 x 490 x 220 mm (tap)	380 x 668 x 420 mm (cooler) 170 x 380 x 350 mm (carbonator) 180 x 490 x 220 mm (tap)	370 x 540 x 496 mm	360 x 440 x 360 mm (cooler carbonator) 180 x 490 x 220 mm (tap)
Dispensing height	325 mm				320 mm
Weight	74.5 kg (system) 2 kg (tap)		50 kg (cooler) 13 kg (carbonator) 2 kg (tap)	33.8 kg	35.4 kg (cooler carbonator) 2 kg (tap)
Max. power consumption	1150 W		1817 W	1173 W	
Max. flow rate	3 l/min			2 l/min	
Order number					
	1022755 Bottler 101-2-FS-0 CU GB	1022758 Bottler 102-2-FS-0 CU GB	1022757 Bottler 103-2-TS-0 CU GB	1022756 Bottler 104-2-CT-0 CU GB	1022930 Bottler 105-2-TS-0 CU GB

The food-grade quality and safety of BRITA water filter products are tested and verified by independent institutions



*applies to all materials that come into contact with water

Why BRITA VIVREAU?

Because of the advanced water treatment technologies.



Water is more than simply H₂O. That's why we have developed professional water filtration solutions for over 50 years, with a German passion for quality. Our hygiene features have been tested in a number of long-term studies conducted by independent institutions.



Better taste. Greater safety.

BRITA water filtration and hygiene features.



With BRITA multi-step filtration solutions, you can count on excellent water – delivered to the highest hygiene, quality and environmental standards.

Think water is simply H₂O? Think again: water typically contains a diverse blend of minerals, organic residues and other substances. And that affects how it tastes, looks and smells.

This is where we come in. At BRITA, water is our passion, and has been for over half a century. We have channelled that expertise into our proven BRITA filtration and treatment technology, incorporated into each and every one of our BRITA VIVREAU dispensers.

The result is truly refreshing: you enjoy delicious filtered water with just the right composition of minerals. Plus, BRITA's hygiene safeguards keep it clean, effectively removing bacteria, microbial cysts and more – meeting the strictest safety requirements and giving you peace of mind.



Activated carbon filtration
Reduces substances that impair taste and odour.



Ion exchanger
Reduces limescale and metals e.g. lead.



The right balance
Preserves minerals in water.

CLARITY Taste 50/100/50R/100R

Water filter: Crystal clear water for cold drinks.



The BRITA CLARITY Taste filter unites activated carbon technology with a pre-filter. This dynamic duo preserves minerals in water while removing unwanted substances, such as microplastics and chlorine. The result is crystal-clear water with a reliably refreshing taste. What's more, the filter protects the dispenser against downtime caused by fine particles, such as rust and sand.

BRITA CLARITY Taste 50/100 filters are compatible with:

- VIVREAU Top 15
- VIVREAU Extra 50/85
- VIVREAU Bottler
- VIVREAU Top 50/85
- VIVREAU ViTap
- VIVREAU Fill



The right balance
Preserves minerals in water.

Benefits of BRITA CLARITY Taste



Reduces fine particles such as microplastic or sand



Reduces metals such as lead



Reduces pharmaceuticals, pesticides and hormones



Reduces chlorine taste and odour



Reduces organic impurities



Activated carbon filtration
Reduces substances that impair taste and odour.



Pre-filter
Removes coarse particles.



- **Filter capacity:**
Taste 50: 4,000 l
Taste 100: 11,500 l

- **Perfect-tasting water** with ideal properties

- **Protects equipment** and therefore lowers dispenser maintenance costs

CLARITY Taste 50/100/50R/100R

Technical data



Model	Taste 50	Taste 100	Taste 50R	Taste 100R
Technology	activated carbon filtration			
Water intake temperature	4°C to 30°C			
Ambient temperature for operation	4°C to 40°C			
Ambient temperature for storage/ transport	-20°C to 50°C			
Water inlet and outlet connection	CLARITY filter head JG 8mm		Everpure filter head	
Operating pressure	2 bar to 8.6 bar			
Flow rate at 1 bar pressure loss	180 l/h			600 l/h
Operating flow range and associated pressure loss	40 l/h to 220 l/h 0.2 bar to 1.5 bar	40 l/h to 220 l/h 0.2 bar to 1.3 bar	40 l/h to 220 l/h 0.2 bar to 1.5 bar	40 l/h to 350 l/h 0.1 bis 0.4 bar
Nominal filter capacity	4,000 l	11,500 l	4,000 l	11,500 l
Operating position	horizontal or vertical			
Reduction performance				
Reduction of particles such as micoplastics or sand	≥ 0.5 µm (NSF 42, Class I)			≥ 2.0 µm (DIN EN 13443)
Reduction of metals such as lead	> 90 % (DIN EN 14898)			
Reduction of chlorine	> 90 % (DIN EN 14898, Class I) and > 50 % (NSF 42)			
Reduction of organic impurities such as benzene	> 90 %			
Reduces pharmaceuticals, pesticides and hormones such as naproxen, lindane, estrone	>90% up to at least 4,000 l (CLARITY Taste 50/50R) and 8,000 l (CLARITY Taste 100/100R)			
Dimensions (W x D x H)				
Filter system (filter head with filter cartridge)	68 x 68 x 251 mm	68 x 68 x 338 mm	-	-
Filter cartridge	68 x 68 x 224 mm	68 x 68 x 311 mm	86 x 86 x 226 mm	86 x 88,6 x 317 mm
Installed dimensions (vertical installation with wall mounting bracket)	68 x 74 x 284 mm	68 x 74 x 371 mm	-	-
Product number				
Filter cartridge (pack 1)	1020509	1020569	1020524	1033419
Filter head CLARITY (pack 1)	1024792	1024792	-	-
Certificates	KTW, ACS, TIFQ, WRAS, NSF, Watermark		KTW, ACS, TIFQ	

The food-grade quality and safety of BRITA water filter products are tested and verified by independent institutions



*applies to all materials that come into contact with water

Contact your BRITA authorized distributor in Egypt | www.quanta-egypt.com

CLARITY Protect 100

Water filter: Reliably safe, excellent water for your dispenser.



Drinking water is strictly controlled. But in healthcare and other environments, you often need an extra level of safety. The CLARITY Protect 100 filter was made precisely for these scenarios. It removes bacteria, cysts and more to ensure exceptionally clean, safe water. Together with the CLARITY Safe X3 filter and BRITA ThermalGate™ feature, it forms the BRITA HygienePlus solution.

BRITA CLARITY Protect 100 is compatible with:

- VIVREAU Top 50/85 HygienePlus
- VIVREAU Extra 50/85 HygienePlus



The right balance
Preserves minerals in water.



Hollow fibre membrane
Filters out 99.999% of bacteria and 99.95% of cysts.



Activated carbon filtration
Reduces substances that impair taste and odour.



Pre-filter
Removes coarse particles.



• **Filter capacity:**
Protect 100: 11,500 l

• **Exceptionally clean, safe drinking water**

• **Protects equipment**
and therefore lowers
dispenser maintenance costs

Benefits of BRITA CLARITY Protect



Reduces fine particles such as microplastic or sand



Reduces metals such as lead



Reduces pharmaceuticals, pesticides and hormones



Reduces chlorine taste and odour



Reduces organic impurities



Removes bacteria and cysts

CLARITY Protect 100

Technical data



Model	BRITA CLARITY Protect 100
Technology	activated carbon filtration
Water intake temperature	4°C to 30°C
Ambient temperature for operation	4°C to 40°C
Ambient temperature for storage/ transport	-20°C to 50°C
Water inlet and outlet connection	JG 8 mm
Operating pressure	2 bar to 8.6 bar
Flow rate at 1 bar pressure loss	180 l/h
Operating flow range and associated pressure loss	40 l/h to 220 l/h 0.2 bar to 1.6 bar
Nominal filter capacity	11,500 l
Operating position	horizontal or vertical
Reduction performance	
Reduction of particles such as micoplastics or sand	≥ 0.5 µm (NSF 42, Class I)
Reduction of metals such as lead	> 90 % (DIN EN 14898)
Reduction of chlorine	> 90 % (DIN EN 14898, Class I) and > 50 % (NSF 42)
Reduction of organic impurities such as benzene	> 90 %
Reduces pharmaceuticals, pesticides and hormones such as naproxen, lindane, estrone	> 90 % up to at least 8,000
Reduction of bacteria	99.999% (ASTM F838-05)
Reduction of cysts	99.95% (NSF 53)
Dimensions (W x D x H)	
Filter system (filter head with filter cartridge)	68 x 68 x 338 mm
Filter cartridge	68 x 68 x 311 mm
Installed dimensions (vertical installation with wall mounting bracket)	68 x 74 x 371 mm
Product number	
Filter cartridge (Pack 1)	1020581
Filter head CLARITY (Pack 1)	1024792

The food-grade quality and safety of BRITA water filter products are tested and verified by independent institutions



Product compliant with
Reg. EC No 1935/2004

*applies to all materials that come into contact with water

Contact your BRITA authorized distributor in Egypt | www.quanta-egypt.com

CLARITY Safe X3


A bacterial filter for outstanding hygiene in critical environments.



The CLARITY Safe X3 filter rounds out the BRITA HygienePlus solution. This filter is just upstream of the dispenser outlet tap. So when you draw water, CLARITY Safe X3 removes any potentially remaining bacteria, microbial cysts and other unwanted impurities – right then and there. This final layer of protection guarantees water of outstanding quality and hygiene each and every time you use your dispenser.

BRITA CLARITY Safe X3 is a key component included in:

- VIVREAU Top 50/85 HygienePlus
- VIVREAU Extra 50/85 HygienePlus



Double-layer membrane
Filters out 99.99999% of bacteria and 99.95% of cysts.

Benefits of BRITA CLARITY Safe X3



Reduces fine particles such as microplastics



Reduces fine particles such as sand




Reduction of bacteria



Reduction of cysts

Second safeguard
in combination with CLARITY Protect, filters water when dispensing



Filter capacity:
Filter life of up to 6 months

Maximum safety via asymmetrical double-layer membrane

CLARITY Safe X3

Technical data



Model	BRITA CLARITY Safe X3
Operating pressure	2 bar to 10 bar
Flow rate at 1 bar pressure loss	180 l/h
Nominal filter capacity	exchange after 6 months
Particle retention	0.2 µm (nominal)
Reduction of bacteria	99.99999% (ASTM F838-05)
Reduction of health contaminants such as cysts	99.95% (NSF 53)
Operating position	Horizontal or vertical
Dimensions (W x D x H)	
Filter cartridge	86 x 86 x 112 mm
Product number	
Filter cartridge	1036478 Pack 1 BRITA CLARITY X3 CU

The food-grade quality and safety of BRITA water filter products are tested and verified by independent institutions



Product compliant with
Reg.EC No 1935/2004

*applies to all materials that come into contact with water

PURITY C Dispenser C300/C500/C1100



Water filter: Excellent filtration designed for hot water dispensers.

Need piping-hot water? That's no problem for PURITY C Dispenser. This filter cartridge was specially designed for these situations. It protects the dispenser by reducing carbonate hardness, tackling the common problem of limescale head on. It also removes unwanted, taste-impairing substances. And its IntelliBypass® feature lets you control the degree of hardness – so you have just the right amount, for instance, for a perfect cup of tea.

PURITY C Dispenser filters are compatible with:

- VIVREAU ViTap

Benefits of BRITA PURITY C Dispenser



Reduces fine particles such as sand



Reduces metals such as lead



Reduces carbonate hardness



Reduces chlorine taste and odour



Reduces organic impurities



Post-filter

An extra layer of filtration for perfect results.



Activated carbon filtration

Reduces substances that impair taste and odour.



Ion exchanger

Reduces limescale and metals e.g. lead.



Pre-filter

Removes coarse particles.



• IntelliBypass® for achieving the ideal mineral composition

• Filter capacity:
PURITY C300: 2,784 l
PURITY C500: 5,008 l
PURITY C1100: 8,480 l

• Adjustable water hardness
For great-tasting and great-looking hot drinks

• Protects equipment and therefore lowers dispenser maintenance costs

PURITY C Dispenser C300/C500/C1100

Technical data



Model	BRITA PURITY C Dispenser C300	BRITA PURITY C Dispenser C500	BRITA PURITY C Dispenser C1100
Technology	decarbonisation		
Capacity ¹ water dispensers (at a carbonate hardness of 10°dH/bypass setting of 40%)	2,784 l	5,008 l	8,480 l
Max. operating pressure	2 bar to max. 8.6 bar		
Water intake temperature	4 – 30 °C		
Nominal flow	60 l/h	100 l/h	
Pressure loss at nominal flow	0.25 bar	0.5 bar	
Dimensions (W x H x D) Filter head with filter cartridge	125 x 119 x 466mm	144 x 144 x 557mm	184 x 184 x 557mm
Weight (dry/wet)	2.8/4.2 kg	4.6/6.9 kg	7.7/12.5 kg
Connections (input/output)	G 3/8" or John Guest 8 mm		
Operating position	horizontal and vertical		
Product number			
Filter cartridge (pack 1)	1025301	1025302	1025303
Filter head 0 – 70 %, JG 8	1013636 (pack 1) 1013633 (Pack 20)		
Accessories: BRITA FlowMeter 10 – 100	1033041		
Accessories: Hardness test kit (carbonate)	710800		

¹ The capacities given have been tested and calculated on the basis of normal application and machine conditions. Due to external influences (e.g. variations in raw water quality and/or machine type), deviations from these results can occur.

The food-grade quality and safety of BRITA water filter products are tested and verified by independent institutions



*applies to all materials that come into contact with water

Contact your BRITA authorized distributor in Egypt | www.quanta-egypt.com

BRITA ThermalGate™

Hygiene feature: BRITA's powerful thermal disinfection solution.




The tap of a typical water dispenser is exposed: a sneeze or touch of a hand, for example, can introduce germs. Without a robust safeguard, microorganisms on the wet tap can go on to contaminate the dispenser. That's why our BRITA VIVREAU dispensers include our ThermalGate™ feature. This automatically and regularly heats the tap to disinfect it. So you can sit back and relax – knowing you have a proactive, powerful defence against germs, tried and tested by an independent laboratory (Hygiene Institut des Ruhrgebiets).



ThermalGate™
Protects against retrograde contamination.

The tap is automatically heated to over 125°C at regular intervals for thermal disinfection.



ThermalGate™ is continuously active, •
providing protection not only at peak times,
but also during periods of inactivity, e.g. at
night or on weekends

Does not require manual effort or chemical •
additives

Developed on the basis of over 20 years' •
experience in the healthcare market.



BRITA HygienePlus

Hygiene feature: Proven three-zone-protection for special hygiene requirements.



Our special BRITA HygienePlus solution consists of three safeguards. Together, they deliver the outstanding degree of protection needed in hygiene-sensitive environments. In fact, we developed it based on over 20 years' experience in the healthcare market. BRITA HygienePlus removes bacteria and microbial cysts, so you enjoy safe, great-tasting water at all times. Plus, BRITA HygienePlus has been tested in multiple studies at hygiene institutes, including at University Medical Center of the Johannes Gutenberg University Mainz, confirming e.g. compliance with DVGW-W 516.

Benefits of BRITA HygienePlus

1. The first step is the BRITA CLARITY Protect filter. This cartridge combines a pre-filter with activated carbon and hollow-fibre membrane technologies. With a pore size of just 0.15 μm , it reliably retains any potential bacteria and cysts, in line with NSF 53. Plus, it reduces turbidity, metals e.g. lead, and taste-impairing substances e.g. chlorine.
2. Next up is BRITA CLARITY Safe X3. This filter - located directly upstream of the dispenser tap - is a very fine, asymmetrical double-layer membrane that retains any potentially remaining bacteria and cysts just before the water is drawn.
3. Last but not least, BRITA's powerful ThermalGate™ feature automatically and regularly heats the dispenser outlet tap. This protects against contamination from external sources, such as physical contact (e.g. touching the tap) and droplets (e.g. from sneezing or coughing).



Why BRITA VIVREAU?

Because it's an end-to-end solution.



The most important argument in the dispenser's favour: BRITA VIVREAU is a complete solution. There's the dispenser, combined with customised bottles. Everything was installed by professional service engineers. And I could choose a flexible rental option to accommodate future growth at my company.



A comprehensive range of accessories



Find your ideal and sustainable BRITA accessories to complement your BRITA VIVREAU dispenser.


The water dispenser is only one part of the picture: take advantage of BRITA products across the entire water dispensing-serving-cleaning cycle.

When you want to enjoy or serve great-tasting water, BRITA VIVREAU has your back every step of the way.

We provide premium customisable and reusable bottles that can be readily refilled via our dispensers. Where needed, the bottles can be stored in special crates precisely designed for the various types of BRITA designer bottles. Clean, filled bottles and used empties can be placed in separate, dedicated crates.

Furthermore, hygiene is always the top priority. We therefore provide all equipment necessary to properly sanitise BRITA VIVREAU dispensers and BRITA bottles. For bottles, we offer a choice of washing trays, including versions compatible with professional and domestic dishwashers.

And our best-practices tip: we recommend cleaning BRITA VIVREAU dispensers daily for extra peace of mind.



Are you looking for ways to shrink your carbon footprint?

Replacing plastic bottles with long-lasting BRITA bottles and corresponding accessories is an easy way to make a difference.



Customisable BRITA bottles

Sustainable BRITA bottles and dispenser solutions: the perfect pairing.



Make your BRITA bottle your very own.

Customised high-quality bottles are ideal for a variety of scenarios. Placed on meeting or restaurant tables, for instance, they provide a great opportunity to prominently position a logo or raise awareness of a particular message.

The glass designer bottles come in a variety of sizes and styles, so you can find the right option for your organisation's needs.

Additionally, reusable bottles are a stand-out way to communicate your commitment to the environment. Eliminating single-use plastic bottles helps shrink carbon footprints and makes a statement – and now more than ever, it's something your employees, guests and clients will recognise and appreciate.

At the same time, giving up pre-bottled drinks does not mean your water is any less refreshing: our dispensers simply and efficiently chill water on demand.

Customisable BRITA bottles

Elegant presentation of your freshly filtered water.



Wave Bottle



Classic Bottle



BRITA Wave Bottle	
Sizes	600 / 750 / 850 ml
Material	Coated glass (750 ml) / Durable plastic (850 / 600 ml)
Cap	• Colour: white or grey
Customised print on cap	With or without still/sparkling icons
Minimum order quantity	12 standard or 60 customised BRITA Wave bottles
Customised print	Up to two colours (bottle and/or cap, dishwasher-resistant)

BRITA Classic Bottle	
Sizes	500 / 750 / 1,000 ml
Material	Coated glass
Seal	• Colour: white (porcelain) • Seal colour: blue or green
Minimum order quantity	20 standard or customised BRITA Classic bottles
Customised print	Up to four colours (dishwasher-resistant)

BRITA accessories



1



2



3

BRITA-exclusive washing trays

1. Professional washing tray	<ul style="list-style-type: none"> • Size (W x H x D): 500 x 360 x 500 mm, 16 bottles • Compatible with: BRITA Swing 425 / 750 ml, BRITA Classic 750 / 1,000 ml • Openings custom-designed for the bottle neck
2. Professional washing tray incl. cap holder	<ul style="list-style-type: none"> • Size (W x H x D): 500 x 330 x 500 mm, 16 bottles • Compatible with: BRITA Twist 700 ml • Openings custom-designed for the bottle neck
3. Domestic washing tray	<ul style="list-style-type: none"> • Size (W x H x D): 485 x 180 x 485 mm, 25 bottles • Compatible with: all BRITA bottles (for BRITA Classic/Swing 750 ml and 1,000 ml it may be necessary to remove the top tray of the dishwasher) • Custom tines to hold the bottles, fits into the bottom tray of most domestic dishwashers



1



2



3



4



5



6

Further bottle cleaning equipment

1. Professional washing tray	<ul style="list-style-type: none"> • Size (W x H x D): 500 x 365 x 500 mm, 16 bottles • Compatible with: BRITA Swing 750 ml, BRITA Classic 750 / 1,000 ml
2. Professional washing tray	<ul style="list-style-type: none"> • Size (W x H x D): 500 x 295 x 500 mm, 25 bottles • Compatible with: BRITA Wave 600 / 750 / 850 ml, BRITA Twist 700 ml, BRITA Lounge 750 ml
3. Professional washing tray (small)	<ul style="list-style-type: none"> • Size (W x H x D): 400 x 280 x 400 mm, 16 bottles • Compatible with: BRITA Wave 600 / 750 / 850 ml, BRITA Twist 700 ml, BRITA Classic 500 ml
4. Professional washing tray	<ul style="list-style-type: none"> • Size (W x H x D): 500 x 325 x 500 mm, 25 bottles • Compatible with: BRITA Swing 425 ml, BRITA Classic 500 ml
5. Professional washing tray	<ul style="list-style-type: none"> • Size (W x H x D): 500 x 500 x 220 mm, 36 bottles • Compatible with BRITA Lounge 350 ml
6. Cleaning brush	<ul style="list-style-type: none"> • Size (W x L_{total}, L_{brush}): 65 x 500 mm, 160 mm • Compatible with: all BRITA bottles



1



2

Storage crates

1. 6-bottle crate	<ul style="list-style-type: none"> • Solid storage crate, stackable • Size (W x H x D): 300 x 380 x 200 mm, 6 bottles • Compatible with: BRITA Swing 750 ml, BRITA Twist 700 ml, BRITA Classic 750 / 1,000 ml, BRITA Lounge 350 / 750 ml
2. 12-bottle crate	<ul style="list-style-type: none"> • Solid storage crate, stackable • Size (W x H x D): 300 x 340 x 400 mm, 12 bottles • Compatible with: all BRITA bottles except BRITA Swing 750 ml

The BRITA VIVREAU service package

Expert, reliable advice and assistance.




Our BRITA service package keeps your water dispenser in optimal condition, and helps you avoid costly downtime and reactive maintenance costs.

You can take advantage of a premium end-to-end water-dispenser solution – comprising a range of services, a dedicated customer-care team, and a national team of BRITA service engineers. We support you throughout the entire lifecycle of your dispenser, from the on-site survey and installation, to training, maintenance and servicing.

We are a one-stop shop for your organisation's specific drinking water needs – from advising you on the best dispenser model for your requirements, to installing and commissioning, to providing regular servicing. Twice-annual maintenance helps to ensure correct operation and effective hygiene.

Benefits

- End-to-end solution – giving you peace of mind at all times.
- Proactive approach – filter replacement keeps your equipment and water at its best.
- Customer-care team – manages services across your dispenser's entire lifecycle.



What do our customers think?



We are very happy about this innovation. It allows us to continue on our way for a better and cleaner environment and less plastic waste. I want to thank Quanta Egypt for the excellent service. They responded very quickly, where always open for our questions and suggestions and they share our understanding for environment protection. We are really looking forward to a great and long cooperation.

General Manager | The Breakers
Stefan Reichl

Not only did installing BRITA Dispensers provide us with the option of drinking fresh tasting temperature controlled water at the office but the carbonated option proved to be a refreshing and invigorating alternative which I personally enjoy. Moreover, by installing a dispenser on every floor of the building helped the company cut plastic bottle consumption by over 90% which is great for sustainability and makes us feel so much better about protecting the environment. Financially, the return on investment turned out to be in the neighborhood of around 18 months from purchase. By eliminating plastic water bottle truck deliveries to the office we even reduced our carbon footprint!

Chief Operating Officer | Sodic
Shehab El Orabi

For more information please contact:

BRITA Authorized Distributor:

QUANTA:

22 Syria Street | Mohandessin | 8th Floor | Cairo, Egypt.

Tel. +202 33384330 | +202 33358102 | +20 12 27427682 | salesupport@quanta-egypt.com

Facebook: [quantabeverages](https://www.facebook.com/quantabeverages) | www.quanta-egypt.com

QUANTA[®]

